

1.1 PRODUCING AND STOCKPILING DESIGNATION 4 AGGREGATE BY CUBIC METRE

When the Contract calls for the production and stockpiling of Designation 4 crushed aggregates on a cubic metre basis, the following shall apply:

- (a) Contrary to Section 3.2.3.3(viii) of Specification 3.2, Aggregate Production and Stockpiling, stacking conveyors may not be used for stockpiling the aggregate.
- (b) Contrary to paragraph 2 of Section 3.2.4.2 of Specification 3.2 Aggregate Production and Stockpiling, cubic metre measurement and payment for producing and stockpiling crushed aggregate will be made as follows:

1.1.1 Measurement

The Consultant will take original and final measurements only.

Original measurements will be made by cross-sectioning the completed stockpile base constructed by the Contractor.

Final measurements will be determined by cross-sectioning the completed stockpile. No allowance will be made for settlement of the stockpile or the stockpile base.

The Contractor shall notify the Consultant when the stockpile base is constructed and when the stockpile is completed so that measurements can be taken. The Contractor shall ensure that the volume of the completed stockpile is a minimum of 95% of the tender amount prior to requesting final measurement.

1.1.2 Payment

Payment will be made at the applicable unit price bid for the quantity measured, up to a maximum of the tender amount.

Quantities measured in excess of the tender amount and up to 110% of the tender amount will be paid for at 66% of the applicable unit price bid.

Quantities measured in excess of 110% of the tender amount will not be paid for but will be the property of the Department.

Payment will include full compensation for constructing the stockpile base, excavating and loading to crusher, processing, hauling and stockpiling the aggregate in accordance with the specifications.